

2015 1-Ton 4 X 4 Service Truck: Specifications
Chassis Only – Bed by Others
Super Cab Dually

F350 SD or Equivalent
White
40/20/40 Vinyl Seats

Preferred Equipment Package

- XL Trim
- Interior Power Package
- Electronic Shift on the Fly 4 X 4
- Trailer Tow Package
- Camper Package
- Suspension with Stabilizing Bar
- Trailer Brake Controller
- Truck Cab Interior Auxiliary Switch
- Radio
- Vinyl Flooring
- Dual Rear Wheel Axle

Engine: ● 6.2 V8 Gas or Equivalent
Trans: ● 6-speed Automatic
● 3.73 Rear Axle
● 162" Wheel Base

LT245/R17E All Season Tires
Spare Tire, Wheel and Jack
12.5K Trailer Hitch
11400 GVWR Package
Truck Tube Steps

See Service Body Specifications for Additional Emergency Lighting

**Specifications: for Service Body
Knapheide Service Body 7108D54J1 or Equivalent**

- Electro-coat Prime System
- Undercoated
- Painted Single Stage, Single White
- 12" Pickup Style Tailgate
- Stainless Steel Rotary Latches
- Tread Plate Steel Pintle Hook Recess Bumper
- LED Flush Mount Light Kit
- Chrome Gas Pod
- Tread Plate Aluminum 8" X 16", on Lower Front Corners
 - Length: 9"
 - Width: 94"
 - Compartment Height: 40"
 - Compartment Depth: 20"
 - Floor Width: 54"

Compartmentation:

- Street and Curb Side Front Verticles: Two Adjustable Shelves
- Street Side Center Horizontal: No Shelving
- Curb Side Center Horizontal: One Adjustable Shelf
- Street and Curb Side Rear Verticles: One Adjustable Shelf
- Back up Alarm: Installed

Options:

- Hitch, Receiver Class V 2.5" with 2" Adapter and 7-wire Plug
- 2" Ball/pintle Combo Hitch
- 72" Shovel Box (Loose in Service Body Floor)
- Vise Bracket Installed Curb Side Rear Bumper
- Cab Guard with Light Bracket
- Sprayed in Bed Liner
- (1) Ecco 5580CA LED Amber Strobe Light
- (4) Ecco 3861A LED Amber 6" Strobe Lights 2 at Grill and 2 at Rear

Goodall Power Center GPC 1150 or Equivalent

New Model: GPC 01-150

(Welder, AC Generator and Air Compressor)

Dimensions: 50"L x 23W x 45"H, 675 lbs.
Engine: Air cooled Kohler command OHV V-twin with 5 gal. fuel tank
DC Welding: DC Stick 40-250 amp - 250 amp 60% duty cycle
Cables: 24 ft. 1/0 ga. welding cables included
AC Power: 110/220 volt, 6 KVA, 60 hz
Air Power: 2 stage 29 CFM @100 psi, 175 max, 30 gallon air storage tank
Remote Control Box: 190-007-12 Remote Control Box Assembly, 12"